




GPS NOTE:
The survey shown hereon is based on GPS data collected by Miller, Tungate Land Surveying, LLC. using both Static and RTK methods with dual frequency Carlson BR6+ and BR7 receivers. Data was also collected using conventional EDM equipment. The Kentucky Single Zone Coordinate, NAD 83 was used for coordinate system. Acceptable positional tolerances were achieved by redundant measurements on all GPS control points.

LINE TABLE

LINE	BEARING	DISTANCE
L1	S 34°27'28" W	40.00'
L2	S 55°32'32" E	25.00'
L3	S 34°27'28" W	60.27'

EASEMENT TABLE

LINE	BEARING	DISTANCE
E1	N 49°08'05" E	265.94'
E2	N 49°08'05" E	256.64'
E3	N 34°23'00" E	6.28'
E4	N 34°23'00" E	290.21'
E5	N 52°36'32" E	110.16'



LEGEND

- Iron Pin
(1/2 inch rebar 18 inches long, with cap marked TUNGATE 3997) set this survey unless otherwise noted.
- △ Unmarked point.
- Iron Pin, set as Witness
(1/2 inch rebar 18 inches long, with blue cap marked WITNESS PT, PLS 3997)
- ⊗ Existing Iron Pin and Cap
TUNGATE 3997
- Existing Iron Pin and Cap
DABNEY 1069/3319

PLAT OF SURVEY FOR
GRAYBEAL FAMILY FARMS, LLC
LAND DIVISION #2
JULY, 2023
1631 PALESTINE ROAD
CAMBELLSVILLE, KENTUCKY 42718
PROPERTY LOCATION:
KY HWY 55/70 AND US HWY 68
NEW LEBANON ROAD AND
KY HWY 3211 - PALESTINE ROAD
TAYLOR COUNTY, KENTUCKY
PVA #: 51-005
PART OF DEED BOOK 308, PAGE 807

CLIENT:
GRAYBEAL FAMILY FARMS, LLC
REGISTERED AGENT:
JAMES H. GRAYBEAL
1631 PALESTINE ROAD
CAMBELLSVILLE, KENTUCKY 42718

SCALE: 1 INCH = 100 FEET
100 50 0 100
GRAPHIC SCALE

SURVEY COMPLETED: JULY 20, 2023
DATE OF PLAT: JULY 26, 2023
THIS SURVEY COMPLIES WITH 201 KAR 18:150
MILLER, TUNGATE LAND SURVEYING, LLC.
202 BROOKSIDE AVE
CAMBELLSVILLE, KY 42718
PHONE: (270) 465-2831 044JG23